



# ***Borough of Chambersburg***

*A full service municipality in Franklin County  
celebrating over 65 years of consumer owned natural gas service  
over 100 years of community electric and a  
regional wastewater, water, and municipal solid waste utility*

## **NOTICE OF RECEIPT**

**I have received the Addendum #1 for the Proposal, Specifications, and Contract for Catherine Street Storm Sewer Improvements**

---

Company

---

Contact Person

---

Date Received



# ***Borough of Chambersburg***

*A full service municipality in Franklin County  
celebrating over 65 years of consumer owned natural gas service  
over 100 years of community electric and a  
regional wastewater, water, and municipal solid waste utility*

## **Catherine Street Storm Sewer Improvements (Addendum #1)**

In accordance with the requirements of the "Instructions to Bidders," this Addendum shall be attached to and become a part of the Contract Documents for the above referenced project.

---

### **1. MS-944 Form**

- **Description of Work:** A junction pipe junction will also be replaced with a cast in place manhole, or a fabricated fitting at 3<sup>rd</sup> Street has been replaced with **"An existing pipe junction will also be replaced with a cast in place inlet at 3<sup>rd</sup> Street."**
- Item No. 2 Approximate Quantities has been changed from 4 each to **"3 each."**
- Item No. 4 Approximate Quantities has been changed from 3 each to **"2 each."**



# ATTACHMENT 1

## TO MS - 944 ( PROPOSAL AND CONTRACT MS - 944 )

County: Franklin County

Municipality: Borough of Chambersburg

Project Number: n/a

**LOCATION OF WORK:**

East Catherine Street Storm Sewer Replacement

**DESCRIPTION OF WORK:**

The Borough of Chambersburg is seeking bids for the East Catherine Street Storm Sewer Replacement Project. The project limits are from Water Street to a high line railroad crossing on East Catherine Street. The project scope includes removal of approximately 448 linear feet of pipe (composed of 15" dia. Corrugated Metal Pipe, 15" dia. terra-cotta pipe, and 15" x 17" brick box culvert) and removal/replacement of two existing storm inlet boxes. The existing pipe will be replaced with approximately 448 linear feet of 15 inch HDPE pipe and two new inlet boxes will be poured in place. An existing pipe junction will also be replaced with a cast in place inlet at 3rd Street.

ESCALATOR CLAUSE:( if adopted by Municipality.)

**THIS PORTION TO BE COMPLETED BY THE MUNICIPALITY**

### SCHEDULE OF PRICES

1 Item No.	2 Approximate Quantities	3 Unit	4 *Description	5 Unit Price	6 Total
1	448	LF	15" HDPE Solid Storm Pipe (includes all items in the Trench Restoration Pavement and Storm Trench Details and Grouted penetration at Existing Inlet)		
2	3	EA	2' x 4' Standard Poured-in-Place Inlet Box (2 Near High Line, 1 at Pipe Junction)		
3	448	LF	15" CMP/15" Terra-Cotta/15" x 17" brick box Pipe Removal (includes asphalt and spoils removal/proper disposal of waste)		
4	2	EA	Remove Existing Inlet Box (includes disposal)		
5	1	LS	Traffic Control per PennDOT Pub. 203		

**\* DESCRIPTION:**

**Must include ADT on wearing surfaces  
USE OF CUTBACK ASPHALT IS PROHIBITED  
BETWEEN MAY 1st AND OCTOBER 31st, EXCEPT  
AS NOTED IN BULLETIN NO. 25.  
FOR OPTION OR PHASE BIDS THE TOTALS FOR  
EACH MUST BE INCLUDED.**

	SUBTOTAL
SUBTOTAL FROM OTHER ATTACHMENTS	
BID TOTAL FOR A NON OPTION / PHASE BID	
OPTION 1 OR PHASE 1 BID TOTAL	
OPTION 2 OR PHASE 2 BID TOTAL	
OPTION 3 OR PHASE 3 BID TOTAL	